

Project Note

Baker

Subject: **CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring**

To: Lynn de George, ConocoPhillips and Maggie Valentine, Weston Solutions

From: Jeff Baker and Garrett Yager 2/21/2014

2013 Colville River Delta Spring Breakup Monitoring and Hydrologic Assessment (A component of the CD5 Adaptive Management Strategy) 135141

Contents

1.	Introduction	1
2.	Objectives.....	1
3.	Survey Extents.....	1
4.	Methods.....	3
4.1	Survey Control.....	3
4.2	Transects	3
4.3	Detailed Edge of Bank Delineation	3
5.	Transects	6
6.	Detailed Edge of Bank Delineation	6
6.1	Nigliq Channel Proposed CD5 Bridge Crossing	6
1.	West Bank	6
2.	East Bank.....	7
6.2	Nigliagvik Proposed CD5 Bridge Crossing	8
1.	West Bank	8
2.	East Bank.....	9

Attachment A	Channel and Bridge Transect Survey Results.....	A.1
Attachment B	Daily Field Reports	B.1
Attachment C	Nigliq Channel Bank Surveys.....	C.1
Attachment D	Nigliagvik Bank Surveys.....	D.1

1. Introduction

The U.S. Army Corps of Engineers permit to develop the CD5 infrastructure in the Colville River Delta requires ConocoPhillips Alaska, Inc. to implement a monitoring plan with an adaptive management strategy. The CD5 Monitoring Plan was developed to monitor changes in site conditions relating to the hydrologic functions of the Colville River Delta. Erosion Control Monitoring and Bridge Monitoring are components of the CD5 Monitoring Plan and require pre-construction (baseline) data collection in 2013.

2. Objectives

The Nigliq Channel and Nigliagvik pre-construction bank topography and channel bathymetry was surveyed to establish baseline data for the Erosion Control Monitoring component of the CD5 Monitoring Plan. In addition, pre-construction topographic and bathymetric surveys were performed at the Nigliq Channel, Lake L9341, and the Nigliagvik proposed CD5 bridge crossings to establish baseline data for the Bridge Monitoring component of the CD5 Monitoring Plan. A detailed edge of bank delineation was surveyed in close proximity to the Nigliq Channel and the Nigliagvik proposed CD5 bridge crossings for monitoring bank erosion associated with bridge hydraulics. The purpose of the detailed edge of bank delineation is to identify rapid rates of erosion near the bridges that may require mitigative action.

This project note includes the methods and results from the channel and bridge transect surveys and the detailed edge of bank delineation at the Nigliq Channel and Nigliagvik proposed CD5 bridge crossings. An explanation of how the edge of bank was determined and a detailed description of the pre-construction bank conditions near the Nigliq Channel and Nigliagvik proposed CD5 bridge crossings are also included.

3. Survey Extents

Bank topography and channel bathymetry associated with the Erosion Control Monitoring Study were collected at 14 predetermined transects on the Nigliq Channel and 18 predetermined transects on the Nigliagvik as specified in the CD5 Monitoring Plan and shown in Figure 3.1. Transect spacing is approximately 1,600 feet and extends approximately 9,000 feet upstream and downstream of the proposed bridge centerlines. The Bridge Monitoring study includes 1 additional transect downstream of the Nigliq Channel proposed CD5 bridge crossing, 4 transects at the Lake L9341 proposed CD5 bridge crossing, and 2 additional transects downstream of the Nigliagvik proposed CD5 bridge crossing (Figure 3.1). The detailed edge of bank delineation extends between transects 7 and 11 on the west bank of the Nigliq Channel, between transects 9 and 11 on the east bank of the Nigliq Channel, and between transects 23 and 28 on both banks of the Nigliagvik.

Project Note

Baker

Page | 2

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring




Figure 3.1: Transect Locations

4. Methods

4.1 Survey Control

LCMF used a combination of conventional leveling and static Global Positioning System (GPS) techniques to establish a broad primary control network that encompassed the entire project area. The static survey was then processed using GPS software and the Online Positioning User Service network to derive the North American Datum of 1983 (2011) coordinates. Leveled elevations from local benchmarks were used to bring the project's vertical datum to the desired British Petroleum Mean Sea Level. The carefully thought out location of the primary control points allowed LCMF to use GPS Real Time Kinematic (RTK) surveying techniques to set two secondary control points on each end of all transects and maintain the stringent horizontal and vertical tolerances required for the project. Secondary control points were setback 50 feet and 200 feet from channel banks on the Nigliq Channel and setback 50 feet and 100 feet from channel backs on the Nigliagvik (Figure 3.1).

4.2 Transects

Transects were surveyed by LCMF August 29 through September 18, 2013. Transect bathymetric and topographic data was collected at a minimum spacing of 100 feet in areas of consistent grade and at breaks in grade including the top and toe of the channel banks. Transect stationing was referenced to the 200 foot left bank secondary control point on the Nigliq Channel and the 100 foot left bank secondary control point on the Nigliagvik. Survey markers (pins or marking whiskers), were placed in the ground at survey points between the 50 foot secondary control point and the edge of the channel bank. Survey equipment used for the transect surveys was a combination of Trimble GPS RTK units and a Garmin 178C with a fathometer for the bathymetry portion. The careful planning put forth for the initial survey will allow LCMF to duplicate similar results over the life of the project.

4.3 Detailed Edge of Bank Delineation

The detailed edge of bank delineation survey was conducted by a Michael Baker Jr. Inc. (Baker) hydrologist and LCMF surveyors on August 21 and August 22, 2013. The detailed edge of bank delineation on the Nigliq Channel was referenced to a baseline connecting the 200 foot secondary control points between transects 7 and 11 on the west bank and transects 9 and 11 on the east bank (Figure 4.1). The detailed edge of bank delineation on the Nigliagvik was referenced to a baseline connecting the 100 foot secondary control points between transects 23 and 28 (Figure 4.2). 100 foot stationing was established along the detailed bank delineation baseline. Edge of bank topographic data was collected where a perpendicular projection of the 100 foot stationing intersects the edge of bank. Survey markers (whiskers) were placed in the ground at the survey points delineating the edge of the bank.

Project Note

Baker

Page | 4

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring




Figure 4.1: Baseline for Detailed Edge of Bank Delineation on the Nigliq Channel

Project Note

Baker

Page | 5

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring




Figure 4.2: Baseline for Detailed Edge of Bank Delineation on the Nigliagvik

Project Note

Baker

Page | 6

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

5. Transects

The channel and bridge transect survey results are included in Attachment A.

6. Detailed Edge of Bank Delineation

6.1 Nigliq Channel Proposed CD5 Bridge Crossing

1. West Bank

Top of bank composition downstream of the CD5 bridge crossing is patterned, wet sedge meadow tundra. Banks are characterized by active sloughing with prominent tension cracks. No exposed ice lenses or ice wedges were evident during the time of survey. No large block collapse or thermo-erosional niches were present. Sloughing bank faces were steep and moderately vegetated with scattered drift wood (Photo 6.1). Sloughing bank faces extended to the water line, lacking any exposed beach at the toe of the bank. Edge of bank survey points were positioned at the perimeter of the intact vegetation above the first major tension crack (Photo 6.2).

Bank indentations, formed by ground subsidence likely attributed to melting of underlying ice-wedges, give the bank a scalloped appearance near the proposed CD5 bridge crossing. At these locations, the edge of bank was established above the subsided ground (Photo 6.3).

Downstream of the proposed CD5 bridge crossing, the grade of the sloughing bank was moderate. A beach was observed at the toe as the bank transitioned from a cut bank to a depository bank (Photo 6.4). Tension cracks were evident and similar to the upstream delineation; survey points were established above the first major crack.



Photo 6.1: Sloughing of the Nigliq Channel west bank with scattered drift wood upstream of the proposed CD5 bridge crossing, looking south; August 22, 2013



Photo 6.2: Edge of bank survey point established above the first major tension crack upstream of the proposed CD5 bridge crossing on the west bank of the Nigliq Channel; August 22, 2013

Project Note

Baker

Page | 7

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring



N 70.3021° W 151.0297°

8/22/2013 12:18:39 PM

Photo 6.3: Ground subsidence and defined edge of the Nigliq Channel west bank near the proposed CD5 bridge crossing; looking north; August 22, 2013



N 70.3057° W 151.0299°

8/22/2013 12:51:44 PM

Photo 6.4: Nigliq Channel west bank with beach at toe, downstream of the proposed CD5 bridge crossing; looking southeast; August 22, 2013

2. East Bank

The east bank of the Nigliq Channel upstream of the proposed CD5 bridge crossing is defined as an extensive depository point bar. The point bar is composed of barren ground near the channel and transitions to partially vegetated grasses and dense low willows further from the channel. A gradual break in grade defines the bank from the point bar terrain. The edge of bank survey points were established at the top of the grade break (Photo 6.5).

A small lake basin, just upstream of the proposed CD5 bridge crossing, intersects the floodplain, and a break in grade was not distinguishable between the lake basin and the point bar terrain. At this location, the edge of bank was defined as the eastern edge of the lake. The edge of bank becomes more pronounced near the proposed CD5 bridge crossing as the bank transitions from a depository point bar to a cut bank. Survey points were not established downstream of the proposed CD5 bridge crossing because of restricted access. Visual observations showed the bank maintains a similar profile as the bank at the proposed CD5 bridge crossing for an additional 300 to 400 feet downstream before abruptly transitioning to a cut bank.

Additional visual inspections of the east bank, downstream of the proposed CD5 bridge crossing, were conducted from a boat. Active sloughing, similar to the west bank, was observed. Beyond the downstream extent of the detailed bank delineation limits, thermo-erosional niches (Photo 6.6) and ensuing block collapse (Photo 6.7) were prevalent along the bank.

Daily Field Reports are included in Attachment B and the Nigliq Channel Bank Surveys are located in Attachment C.

Project Note

Baker

Page | 8

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring



N 70.2991° W 151.0198°

8/22/2013 1:44:25 PM

Photo 6.5: Edge of Nigliq Channel east bank defined as top of grade break on point bar, upstream of the CD5 bridge crossing, looking southwest; August 22, 2013



N 70.3124° W 151.0243°

8/22/2013 3:33:41 PM

Photo 6.6: Exposed ice wedge and resulting thermo-erosional niche, west bank of the Nigliq Channel downstream of the proposed CD5 bridge crossing; August 22, 2013



Photo 6.7: Block collapse resulting from thermo-erosional niche, west bank of the Nigliq Channel downstream of the proposed CD5 bridge crossing; August 22, 2013

6.2 Nigliagvik Proposed CD5 Bridge Crossing

1. West Bank

The west bank of the Nigliagvik, upstream of the proposed CD5 bridge crossing, is characterized by steep, sandy bluffs with an overhanging mat of moist sedge-shrub tundra (Photo 6.8). Minor tension cracks were observed in the overhanging tundra mat. Survey points were established where the vegetative mat is anchored to the bluff (Photo 6.9).

Downstream of the proposed CD5 bridge crossing, the gradient of the west bluff becomes moderate. Vegetation is established on the bluff face (Photo 6.10). Survey points were collected at the break in grade defining the top of the bank. Bank indentations, formed by ground subsidence likely attributed to melting of underlying ice-wedges, were encountered downstream of the proposed CD5 bridge crossing. At these locations, the edge of bank was delineated above the subsiding ground (Photo 6.11).

Project Note

Baker

Page | 9

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring



N 70.3040° W 151.1207°

8/21/2013 2:36:31 PM

Photo 6.8: Sandy bluffs and overhanging tundra mat on the east bank Nigliagvik, upstream of the proposed CD5 bridge crossing; looking south; August 21, 2013



N 70.3050° W 151.1205°

8/21/2013 2:46:54 PM

Photo 6.9: Survey point established at anchored edge of the vegetative mat on the Nigliagvik west bluff, upstream of the proposed CD5 bridge crossing; August 21, 2013



N 70.3070° W 151.1191°

8/21/2013 3:26:49 PM

Photo 6.10: Established vegetation on the bluff face of the west bank Nigliagvik, downstream of the proposed CD5 bridge crossing; looking south; August 21, 2013



N 70.3059° W 151.1200°

8/21/2013 3:02:04 PM

Photo 6.11: Nigliagvik west bank indentation downstream of the proposed CD5 bridge crossing; looking south; August 21, 2013

2. East Bank

The east bank of the Nigliagvik is a narrow, muddy depository bank with barren terrain near the channel transitioning to sparsely vegetated mudflats and moist low willow shrub. A break in grade defining the top of bank was not identified. The edge of bank was determined to be at the distinct change in vegetation from sparse grass to dense willows (Photo 6.12). The east bank profile of the Nigliagvik was relatively uniform upstream and downstream of the proposed CD5 bridge crossing. Nigliagvik Bank Surveys are located in Attachment D.

Project Note

Baker

Page | 10

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring



Photo 6.12: East edge of Nigliagvik bank defined where willows are rooted, upstream of the proposed CD5 bridge crossing; looking northeast; August 21, 2013

Project Note

Baker

Page | 11

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

This page intentionally blank.

Project Note

Baker

Page | A.1

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

Attachment A

Channel and Bridge Transect Survey Results

Project Note

Baker

Page | A.2


CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

This page intentionally blank

CD5 TRANSECT CONTROL


NORTHING	EASTING	ELEV	DESCRIPTION	NORTHING	EASTING	ELEV	DESCRIPTION
5,971,410.172	1,507,156.498	8,419	01-LB200 Al Cap Flush	5,963,935.690	1,503,847.826	7,458	20-RB100 Al Cap Flush
5,971,437.585	1,507,303.986	8,293	01-LB50 Al Cap Flush	5,963,972.576	1,503,814.200	7,417	20-RB50 Al Cap Flush
5,971,895.681	1,509,763.370	9,145	01-RB200 Al Cap Flush	5,963,970.128	1,503,127.995	24,412	21-LB100 Al Cap Flush
5,971,868.462	1,509,615.861	9,243	01-RB50 Al Cap Flush	5,963,930.056	1,503,157.752	20,803	21-RB50 Al Cap Flush
5,969,060.233	1,508,196.73	8,815	02-LB200 Al Cap Flush	5,963,562.391	1,503,430.568	8,697	21-RB100 Al Cap Flush
5,969,127.884	1,508,253.550	7,601	02-LB50 Al Cap Flush	5,963,602.565	1,503,400.675	9,087	21-RB50 Al Cap Flush
5,970,206.027	1,510,386.345	9,199	02-RB200 Al Cap Flush	5,963,540.647	1,502,578.286	26,015	22-LB100 Al Cap Flush
5,970,138.191	1,510,452.530	9,108	02-RB50 Al Cap Flush	5,963,500.958	1,502,623.070	23,980	22-RB50 Al Cap Flush
5,967,152.008	1,508,356.949	9,049	03-LB200 Al Cap Flush	5,963,540.585	1,502,899.480	8,555	22-RB100 Al Cap Flush
5,967,172.959	1,509,636.505	10,073	03-LB50 Al Cap Flush	5,962,257.687	1,502,899.410	8,083	22-RB50 Al Cap Flush
5,969,868.861	1,513,117.903	9,529	03-RB200 Al Cap Flush	5,962,089.577	1,502,198.675	26,168	23-LB100 Al Cap Flush
5,968,755.208	1,513,019.945	9,427	03-RB50 Al Cap Flush	5,962,973.595	1,502,246.059	25,141	23-RB50 Al Cap Flush
5,965,610.334	1,510,661.026	12,474	04-LB200 Al Cap Flush	5,962,828.922	1,502,671.946	10,028	23-RB100 Al Cap Flush
5,965,716.671	1,510,772.049	13,761	04-LB50 Al Cap 0.1" BGL	5,962,845.024	1,502,624.761	8,043	23-RB50 Al Cap Flush
5,967,272.757	1,512,396.890	10,303	04-RB200 Al Cap 0.2" BGL	5,962,728.638	1,502,095.588	26,467	24-LB100 Al Cap Flush
5,967,169.027	1,512,288.545	10,193	04-RB50 Al Cap Flush	5,962,717.892	1,502,144.420	27,045	24-RB50 Al Cap Flush
5,964,321.916	1,512,269.778	12,004	05-LB200 Al Cap Flush	5,962,617.894	1,502,598.227	9,107	24-RB100 Al Cap Flush
5,964,413.659	1,513,388.489	13,294	05-LB50 Al Cap Flush	5,962,628.643	1,502,549.427	8,314	24-RB50 Al Cap Flush
5,966,013.949	1,513,346.365	8,712	05-RB200 Al Cap Flush	5,962,627.162	1,502,078.344	27,446	25-LB100 Al Cap Flush
5,965,922.270	1,513,373.997	8,057	05-RB50 Al Cap Flush	5,962,619.301	1,502,456.208	26,188	25-LB50 Al Cap Flush
5,963,381.275	1,512,373.997	11,414	06-LB200 Al Cap Flush	5,962,547.931	1,502,575.399	8,171	25-RB100 Al Cap Flush
5,963,440.005	1,512,512.008	12,999	06-LB50 Al Cap Flush	5,962,555.825	1,502,525.976	8,195	25-RB50 Al Cap Flush
5,964,292.039	1,514,511.947	9,753	06-RB250 Al Cap Flush	5,962,545.484	1,502,058.928	27,484	26-LB100 Al Cap Flush
5,964,233.713	1,514,375.434	10,233	06-RB50 Al Cap Flush	5,962,539.978	1,502,118.584	27,711	26-RB50 Al Cap Flush
5,962,644.637	1,513,005.297	10,674	07-LB200 Al Cap Flush	5,962,497.866	1,502,585.674	9,555	26-RB100 Al Cap Flush
5,962,683.874	1,513,149.989	12,288	07-LB50 Al Cap Flush	5,962,502.417	1,502,535.991	8,293	26-RB50 Al Cap Flush
5,963,144.212	1,514,845.101	10,802	07-RB200 Al Cap Flush	5,962,410.033	1,502,047.844	26,997	27-LB100 Al Cap Flush
5,963,105.009	1,514,700.456	10,098	07-RB50 Al Cap Flush	5,962,406.342	1,502,097.705	27,070	27-LB50 Al Cap Flush
5,961,864.572	1,513,132.749	10,468	08-LB200 Al Cap Flush	5,962,371.997	1,502,567.622	9,566	27-RB100 Al Cap Flush
5,961,851.285	1,513,282.064	10,443	08-LB50 Al Cap Flush	5,962,375.740	1,502,517.808	8,014	27-RB50 Al Cap Flush
5,961,442.215	1,513,168.246	10,511	09-LB200 Al Cap Flush	5,961,986.435	1,502,006.076	21,011	28-LB100 Al Cap Flush
5,961,424.681	1,513,317.350	10,394	09-LB50 Al Cap Flush	5,961,983.639	1,502,055.975	21,72	28-RB50 Al Cap Flush
5,961,244.116	1,514,876.929	9,279	09-RB200 Al Cap Flush	5,961,192.119	1,502,486.658	8,410	28-RB100 Al Cap Flush
5,961,191.912	1,513,104.040	9,867	09-RB50 Al Cap Flush	5,961,937.165	1,502,366.151	9,177	29-LB100 Al Cap Flush
5,961,214.588	1,513,133.884	10,303	10-LB200 Al Cap Flush	5,961,446.941	1,502,073.292	24,206	29-LB100 Al Cap Flush
5,961,195.969	1,513,382.680	10,544	10-LB50 Al Cap Flush	5,961,457.435	1,502,123.177	23,598	29-RB50 Al Cap Flush
5,961,004.246	1,514,808.609	7,234	10-RB200 Al Cap Flush	5,961,559.109	1,502,597.016	8,800	29-RB100 Al Cap Flush
5,961,023.039	1,514,659.848	8,404	10-RB50 Al Cap Flush	5,961,548.659	1,502,548.070	8,629	29-RB50 Al Cap Flush
5,960,173.818	1,512,898.221	10,959	11-LB200 Al Cap Flush	5,960,727.368	1,502,515.791	23,658	30-LB100 Al Cap Flush
5,960,137.662	1,513,043.747	8,787	11-LB50 Al Cap Flush	5,960,728.275	1,502,544.691	23,216	30-LB50 Al Cap Flush
5,959,767.171	1,514,537.179	9,003	11-RB50 Al Cap 0.2" BGL	5,961,239.597	1,502,077.114	10,073	32-LB100 Al Cap Flush
5,958,209.502	1,512,625.605	11,011	12-LB200 Al Cap Flush	5,961,198.806	1,502,848.280	9,549	30-RB50 Al Cap Flush
5,958,123.591	1,512,715.217	11,300	12-LB100 Al Cap Flush	5,960,124.465	1,503,193.305	8,556	31-LB100 Al Cap Flush
5,959,260.248	1,514,746.096	10,244	12-RB200 Al Cap Flush	5,960,172.316	1,503,207.309	9,605	31-LB50 Al Cap Flush
5,959,153.534	1,514,611.534	8,799	12-RB50 Al Cap 0.3" BGL	5,960,896.154	1,503,418.934	10,757	31-RB100 Al Cap Flush
5,955,329.192	1,512,738.181	11,567	13-LB200 Al Cap Flush	5,960,848.113	1,503,404.835	11,123	31-RB50 Al Cap Flush
5,955,412.726	1,512,862.669	12,000	13-LB50 Al Cap Flush	5,959,762.590	1,504,523.205	8,369	32-LB100 Al Cap Flush
5,952,691.471	1,517,145.169	12,611	15-RB50 Al Cap Flush	5,957,571.230	1,505,667.205	12,478	34-LB50 Al Cap Flush
5,957,852.36	1,508,476.551	10,009	16-LB100 Al Cap Flush	5,957,612.244	1,506,316.180	10,539	34-RB50 Al Cap Flush
5,967,804.938	1,506,492.445	9,416	16-LB50 Al Cap Flush	5,956,358.154	1,504,697.383	11,437	32-RB50 Al Cap Flush
5,967,407.545	1,506,622.063	9,108	16-RB100 Al Cap Flush	5,956,412.903	1,506,200.608	12,562	35-LB100 Al Cap Flush
5,967,459.100	1,509,822.749	8,914	16-RB50 Al Cap Flush	5,956,354.426	1,506,246.168	13,026	35-RB50 Al Cap Flush
5,966,866.380	1,502,871.976	8,246	17-LB200 Al Cap Flush	5,955,880.894	1,506,809.410	9,424	36-RB50 Al Cap Flush
5,966,712.363	1,508,294.902	8,485	17-LB50 Al Cap Flush	5,962,715.529	1,510,877.308	8,344	36-LB100 Al Cap Flush
5,966,720.833	1,508,245.661	8,457	17-RB100 Al Cap Flush	5,962,690.391	1,510,921.654	8,055	36-RB50 Al Cap Flush
5,965,609.725	1,502,451.169	8,512	18-LB100 Al Cap Flush	5,962,502.704	1,511,278.621	8,645	36-RB50 Al Cap Flush
5,965,566.257	1,502,475.942	8,621	18-LB50 Al Cap Flush	5,962,603.094	1,510,806.866	8,204	37-LB100 Al Cap Flush
5,965,103.267	1,502,739.379	7,767	18-RB100 Al Cap Flush	5,962,581.024	1,510,851.779	8,345	37-LB50 Al Cap Flush
5,965,146.802							

STA	2013	Future	Description										
0+00	8.4												Ground Shot
1+00	8.4												Ground Shot
2+00	8.1												Ground Shot
2+05	7.5												Top of Bank
2+18	0.0												Toe of Bank/Edge of Water
2+24	-5.5												River Bottom
2+73	-24.2												River Bottom
3+22	-25.0												River Bottom
3+71	-21.3												River Bottom
4+27	-19.0												River Bottom
4+82	-15.5												River Bottom
5+31	-10.0												River Bottom
5+70	-3.7												River Bottom
5+96	0.1												Edge of Water
7+00	4.2												Sand Bar
8+00	5.6												Sand Bar
9+00	6.4												Sand Bar
10+00	6.8												Sand Bar
11+00	7.2												Sand Bar
12+00	6.7												Sand Bar
13+00	5.9												Sand Bar
14+00	2.7												Sand Bar
15+00	2.7												Sand Bar
16+00	2.4												Sand Bar
17+00	1.5												Sand Bar
18+00	0.6												Sand Bar
18+67	0.3												Edge of Water
20+98	-2.9												River Bottom
21+53	-2.6												River Bottom
21+96	-2.8												River Bottom
22+55	-2.8												River Bottom
23+00	-2.6												River Bottom
23+59	-2.6												River Bottom
24+05	-3.4												River Bottom
24+38	0.3												Edge of Water
24+50	7.3												Top of Bank
25+50	8.9												Ground Shot
26+51	9.1												Ground Shot



STA	2013	Future	Description										
0+00	8.9												Ground Shot
1+00	8.7												Ground Shot
1+95	7.2												Top of Bank
2+06	0.7												Edge of Water
2+12	-2.8												River Bottom
2+35	-3.4												River Bottom
2+58	-4.3												River Bottom
2+81	-5.4												River Bottom
3+10	-7.6												River Bottom
3+27	-8.1												River Bottom
3+47	-11.1												River Bottom
3+67	-21.7												River Bottom
3+87	-17.6												River Bottom
4+07	-14.3												River Bottom
4+27	-13.5												River Bottom
4+46	-12.2												River Bottom
4+78	-10.7												River Bottom
4+98	-9.7												River Bottom
5+18	-9.3												River Bottom
5+35	-8.7												River Bottom
5+55	-8.1												River Bottom
5+81	-7.6												River Bottom
6+01	-7.1												River Bottom
6+24	-6.3												River Bottom
6+44	-5.9												River Bottom
6+64	-5.5												River Bottom
6+83	-4.7												River Bottom
7+03	-4.9												River Bottom
7+23	-4.0												River Bottom
7+55	-3.4												River Bottom
7+75	-2.7												River Bottom
7+92	-2.5												River Bottom
8+09	-2.2												River Bottom
8+38	-1.9												River Bottom
8+55	-2.1												River Bottom
8+95	0.8												Edge of Water
10+00	1.8												Sand Bar
11+00	1.9												Sand Bar
12+00	2.0												Sand Bar

STA	2013	Future	Description										
13+00	2.2												Sand Bar
14+00	2.0												Sand Bar
15+00	2.1												Sand Bar
16+00	1.9												Sand Bar
17+00	1.6												Sand Bar
18+00	1.3												Sand Bar
19+00	0.8												Sand Bar
19+81	0.8												Edge of Water
20+84	-2.4												River Bottom
21+07	-2.5												River Bottom
21+36	-2.1												River Bottom
21+53	-2.5												River Bottom
21+72	-2.9												River Bottom
21+85	-2.9												River Bottom
22+01	-4.1												River Bottom
22+21	-4.7												River Bottom
22+38	-5.6												River Bottom
22+55	-6.2												River Bottom
22+75	-4.6												River Bottom
23+11	0.7												Edge of Water
23+16	1.8												Toe of Bank
23+24	7.8												Top of Bank
23+50	8.6												Ground Shot
24+50	9.0												Ground Shot
25+40	9.3												Ground Shot



STA	2013	Future	Description										
0+00	10.0												Ground Shot
1+00	10.8												Ground Shot
2+00	11.4												Ground Shot
2+17	11.1												Top of Bank
2+47	6.4												Toe of Bank
3+00	6.4												Ground Shot
4+00	7.6												Ground Shot
5+00	6.8												Ground Shot
5+25	6.1												Top of Bank
5+74	1.7												Toe of Bank
6+00	1.5												Sand Bar
7+00	3.2												Sand Bar
8+00	4.8												Sand Bar
9+00	5.6												Sand Bar
9+27	5.7												Top of Bank
9+40	2.0												Toe of Bank
10+41	0.2												Edge of Water
10+85	-2.2												River Bottom
10+95	-2.2												River Bottom
11+07	-2.3												River Bottom
11+17	-3.1												River Bottom
11+31	-3.8												River Bottom
11+44	-4.3												River Bottom
11+60	-5.0												River Bottom
11+85	-6.1												River Bottom
12+07	-6.8												River Bottom
12+23	-7.3												River Bottom
12+48	-7.4												River Bottom
12+72	-7.4												River Bottom
12+89	-7.4												River Bottom
13+15	-7.4												River Bottom
13+40	-7.3												River Bottom
13+64	-7.5												River Bottom
13+81	-7.4												River Bottom
14+07	-7.3												River Bottom
14+32	-6.9												River Bottom
14+48	-6.6												River Bottom
14+75	-7.9												River Bottom
14+99	-8.2												River Bottom


STA	2013	Future	Description										
15+16	-8.2												River Bottom
15+42	-8.3												River Bottom
15+61	-8.0												River Bottom
15+86	-8.5												River Bottom
16+02	-8.6												River Bottom
16+27	-8.5												River Bottom
16+51	-8.9												River Bottom
16+75	-8.3												River Bottom
16+98	-8.6												River Bottom
17+14	-8.2												River Bottom
17+39	-7.7												River Bottom
17+63	-7.5												River Bottom
17+85	-7.6												River Bottom
18+02	-7.1												River Bottom
18+28	-7.7												River Bottom
18+53	-7.4												River Bottom
18+69	-7.7												River Bottom
18+96	-8.0												River Bottom
19+12	-6.9												River Bottom
19+37	-6.6												River Bottom
19+53	-7.0												River Bottom
19+80	-7.1												River Bottom
20+04	-7.0												River Bottom
20+19	-7.4												River Bottom
20+43	-7.6												River Bottom
20+60	-6.0												River Bottom
20+82	-5.6												River Bottom
21+04	-5.2												River Bottom
21+19	-4.9												River Bottom
21+31	-3.8												River Bottom
21+50	-2.2												River Bottom
22+00	-0.4												Edge fo Water
22+21	0.4												Toe of Bank
22+32	8.2												Top of Bank
23+00	8.2												Ground Shot
23+22	9.2												Top of Bank
23+36	8.1												Toe of Bank
23+76	7.9												Toe of Bank
23+91	10.0												Grade Break

Calc'd By: AG
Date: 9/30/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects


Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
24+15	10.7													Top of Bank
24+22	8.9													Toe of Bank




STA	2013	Future	Description										
0+00	12.2												Ground Shot
1+00	12.8												Ground Shot
2+00	14.2												Ground Shot
3+00	16.1												Ground Shot
3+91	14.7												Top of Bank
4+24	11.5												Toe of Bank
5+00	12.1												Ground Shot
5+12	12.4												Top of Bank
5+49	8.6												Toe of Bank
5+74	8.3												Toe of Bank
5+83	10.7												Top of Bank
5+91	10.7												Top of Bank
6+04	8.2												Toe of Bank
6+47	7.5												Toe of Bank
6+59	9.7												Top of Bank
7+05	8.0												Top of Bank
7+31	5.3												Toe of Bank
8+00	4.9												Sand Bar
9+00	4.2												Sand Bar
10+00	4.7												Sand Bar
11+00	4.5												Sand Bar
12+00	3.9												Sand Bar
13+00	3.0												Sand Bar
14+00	2.8												Sand Bar
15+00	3.1												Sand Bar
16+00	3.2												Sand Bar
16+62	-0.1												Edge of Water
16+70	-3.1												River Bottom
16+84	-6.0												River Bottom
17+01	-8.6												River Bottom
17+18	-12.4												River Bottom
17+42	-15.3												River Bottom
17+63	-16.5												River Bottom
17+80	-15.7												River Bottom
18+00	-16.4												River Bottom
18+21	-17.6												River Bottom
18+36	-19.2												River Bottom
18+55	-19.3												River Bottom
18+79	-19.9												River Bottom

STA	2013	Future	Description										
18+96	-20.3												River Bottom
19+13	-19.4												River Bottom
19+37	-20.2												River Bottom
19+54	-21.1												River Bottom
19+75	-21.3												River Bottom
19+92	-20.9												River Bottom
20+12	-20.4												River Bottom
20+29	-20.2												River Bottom
20+48	-19.9												River Bottom
20+65	-19.7												River Bottom
20+84	-18.6												River Bottom
21+06	-15.1												River Bottom
21+15	-10.4												River Bottom
21+47	-0.2												Edge of Water
21+91	2.1												Toe of Bank
21+98	10.1												Top of Bank
23+00	10.7												Ground Shot
24+03	10.4												



STA	2013	Future	Description										
0+00	11.9												Ground Shot
1+00	12.0												Ground Shot
2+00	15.5												Ground Shot
3+00	16.1												Ground Shot
4+00	15.4												Ground Shot
4+56	17.2												Top of Bank
4+65	14.2												Toe of Bank
4+81	14.3												Toe of Bank
5+01	18.9												Top of Bank
5+08	18.5												Top of Bank
5+36	13.6												Toe of Bank
5+82	15.9												Top of Bank
6+16	12.6												Toe of Bank
6+92	13.0												Top of Bank
7+20	7.8												Toe of Bank
8+00	5.9												Sand Bar
9+00	5.6												Sand Bar
10+00	6.1												Sand Bar
11+00	5.7												Sand Bar
12+00	4.4												Sand Bar
13+00	3.0												Sand Bar
14+00	2.5												Sand Bar
15+00	2.4												Sand Bar
16+00	1.9												Sand Bar
17+00	2.0												Sand Bar
18+00	1.6												Sand Bar
19+00	1.0												Sand Bar
20+00	1.2												Sand Bar
21+00	0.6												Sand Bar
21+51	-0.5												Edge of Water
21+62	-6.1												River Bottom
21+79	-8.2												River Bottom
21+96	-8.4												River Bottom
22+17	-9.5												River Bottom
22+36	-11.3												River Bottom
22+53	-12.1												River Bottom
22+73	-15.1												River Bottom
22+93	-16.8												River Bottom
23+13	-19.1												River Bottom

STA	2013	Future	Description											
23+30	-21.4													River Bottom
23+49	-22.4													River Bottom
23+73	-22.5													River Bottom
23+93	-22.2													River Bottom
24+10	-22.4													River Bottom
24+29	-22.2													River Bottom
24+53	-23.4													River Bottom
24+70	-23.3													River Bottom
24+87	-20.5													River Bottom
25+04	-21.6													River Bottom
25+18	-20.5													River Bottom
25+30	-16.9													River Bottom
25+47	-8.2													River Bottom
25+74	-0.5													Edge of Water/Toe of Bank
25+87	8.5													Top of Bank
27+00	8.6													Ground Shot
27+70	8.7													Ground Shot




STA	2013	Future	Description										
0+00	11.4												Ground Shot
1+00	11.0												Ground Shot
2+00	14.0												Ground Shot
3+00	15.3												Ground Shot
3+42	17.1												Top of Bank
3+59	12.5												Toe of Bank
4+08	14.8												Top of Bank
4+23	11.1												Toe of Bank
4+96	12.3												Top of Bank
5+11	9.8												Toe of Bank
5+81	7.8												Top of Bank
6+31	1.1												Toe of Bank
7+00	-0.3												Sand Bar
8+00	0.5												Sand Bar
9+00	1.0												Sand Bar
10+00	1.4												Sand Bar
11+00	1.8												Sand Bar
12+00	2.3												Sand Bar
13+00	2.0												Sand Bar
14+24	-0.2												Edge of Water
14+68	-3.3												River Bottom
14+78	-3.1												River Bottom
14+94	-2.8												River Bottom
15+14	-2.4												River Bottom
15+34	-2.8												River Bottom
15+49	-2.6												River Bottom
15+72	-2.9												River Bottom
15+95	-3.5												River Bottom
16+15	-3.3												River Bottom
16+38	-3.8												River Bottom
16+61	-4.1												River Bottom
16+87	-4.1												River Bottom
17+06	-4.8												River Bottom
17+29	-5.3												River Bottom
17+55	-7.2												River Bottom
17+82	-10.0												River Bottom
18+08	-13.4												River Bottom
18+31	-17.8												River Bottom
18+57	-19.9												River Bottom

Calc'd By: AG
Date: 9/30/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects


Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
18+80	-20.3													River Bottom
19+02	-20.8													River Bottom
19+28	-24.5													River Bottom
19+51	-24.1													River Bottom
19+74	-20.4													River Bottom
19+93	-12.5													River Bottom
20+10	-8.6													River Bottom
20+42	-0.3													Edge of Water
20+45	-0.4													Toe of Bank
20+56	8.8													Top of Bank
21+50	9.8													Ground Shot
22+50	9.3													Ground Shot
23+24	9.8													Ground Shot




STA	2013	Future	Description										
0+00	10.6												Ground Shot
1+00	10.1												Ground Shot
1+50	12.2												Ground Shot
1+77	13.4												Grade Break
2+00	11.3												Ground Shot
2+23	8.1												Top of Bank
2+30	2.8												Toe of Bank
2+47	0.6												Edge of Water
4+93	-2.5												River Bottom
5+06	-2.5												River Bottom
5+25	-2.6												River Bottom
5+45	-2.7												River Bottom
5+68	-3.7												River Bottom
5+91	-4.5												River Bottom
6+17	-5.8												River Bottom
6+42	-7.4												River Bottom
6+65	-7.7												River Bottom
6+88	-7.2												River Bottom
7+11	-6.8												River Bottom
7+37	-5.4												River Bottom
7+56	-5.1												River Bottom
7+82	-4.9												River Bottom
8+02	-4.3												River Bottom
8+25	-3.6												River Bottom
8+50	-4.2												River Bottom
8+74	-5.6												River Bottom
9+03	-5.9												River Bottom
9+32	-7.6												River Bottom
9+58	-7.0												River Bottom
9+84	-9.8												River Bottom
10+10	-9.9												River Bottom
10+39	-9.5												River Bottom
10+68	-8.7												River Bottom
10+91	-8.3												River Bottom
11+21	-8.9												River Bottom
11+50	-9.2												River Bottom
11+76	-9.4												River Bottom
12+02	-11.0												River Bottom
12+31	-11.6												River Bottom

STA	2013	Future	Description										
12+57	-10.4												River Bottom
12+83	-9.0												River Bottom
13+09	-8.4												River Bottom
13+35	-7.6												River Bottom
13+64	-6.7												River Bottom
13+87	-6.3												River Bottom
14+17	-5.7												River Bottom
14+40	-5.9												River Bottom
14+69	-6.6												River Bottom
14+98	-7.8												River Bottom
15+24	-10.7												River Bottom
15+53	-13.6												River Bottom
15+79	-14.7												River Bottom
16+02	-11.1												River Bottom
16+84	0.7												Edge of Water
16+95	8.5												Top of Bank
17+00	9.2												Ground Shot
17+57	10.1												Ground Shot
18+00	9.4												Ground Shot
19+00	10.2												Ground Shot
19+07	10.8												Ground Shot



STA	2013	Future	Description										
0+00	10.6												Ground Shot
1+00	10.1												Ground Shot
2+00	9.8												Ground Shot
2+08	8.9												Top of Bank
2+24	0.9												Edge of Water
2+99	-5.8												River Bottom
3+20	-7.1												River Bottom
3+40	-7.4												River Bottom
3+61	-8.2												River Bottom
3+85	-9.7												River Bottom
4+09	-9.9												River Bottom
4+33	-9.9												River Bottom
4+57	-10.3												River Bottom
4+85	-10.0												River Bottom
5+09	-10.6												River Bottom
5+33	-11.5												River Bottom
5+60	-11.9												River Bottom
5+87	-12.4												River Bottom
6+19	-11.8												River Bottom
6+46	-11.1												River Bottom
6+73	-11.2												River Bottom
7+01	-10.3												River Bottom
7+28	-10.0												River Bottom
7+53	-11.8												River Bottom
7+80	-11.6												River Bottom
8+08	-12.1												River Bottom
8+36	-11.6												River Bottom
8+59	-11.0												River Bottom
8+79	-11.1												River Bottom
9+04	-9.1												River Bottom
9+28	-8.3												River Bottom
9+53	-8.1												River Bottom
9+76	-7.7												River Bottom
9+96	-7.6												River Bottom
10+17	-7.2												River Bottom
10+42	-5.6												River Bottom
10+62	-3.1												River Bottom



STA	2013	Future	Description										
0+00	10.6												Ground Shot
1+00	9.9												Ground Shot
1+50	10.5												Ground Shot
1+92	9.6												Top of Bank
2+07	0.6												Edge of Water
2+48	-5.7												River Bottom
2+62	-7.7												River Bottom
2+78	-10.5												River Bottom
2+92	-14.5												River Bottom
3+13	-15.5												River Bottom
3+33	-15.2												River Bottom
3+58	-14.8												River Bottom
3+79	-13.9												River Bottom
4+03	-13.9												River Bottom
4+26	-13.4												River Bottom
4+54	-12.9												River Bottom
4+78	-13.4												River Bottom
5+02	-13.0												River Bottom
5+30	-13.2												River Bottom
5+54	-13.9												River Bottom
5+79	-13.7												River Bottom
6+02	-12.6												River Bottom
6+30	-12.2												River Bottom
6+55	-12.7												River Bottom
6+79	-15.2												River Bottom
7+06	-14.0												River Bottom
7+30	-13.3												River Bottom
7+57	-11.9												River Bottom
7+84	-11.6												River Bottom
8+08	-11.0												River Bottom
8+33	-9.9												River Bottom
8+58	-6.9												River Bottom
8+78	-5.2												River Bottom
8+91	-3.3												River Bottom
9+41	0.5												Edge of Water
10+00	2.3												Sand Bar
11+00	3.9												Sand Bar
11+52	5.0												Edge of Vegetation
12+00	5.4												Ground Shot
13+00	4.2												Ground Shot

Calc'd By: CZ
Date: 10/03/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
14+00	3.9													Ground Shot
14+39	3.7													Edge of Water
14+81	3.4													Edge of Water
14+84	3.8													Toe of Bank
15+00	5.7													Top of Bank
15+52	8.0													Ground Shot
16+00	8.2													Ground Shot
16+92	9.4													Ground Shot


Calc'd By: CZ

Date: 10/03/13

RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
Doc: LCMF-156 REV1




STA	2013	Future	Description										
0+00	10.3												Ground Shot
1+00	10.4												Ground Shot
1+50	10.5												Ground Shot
1+90	9.9												Top of Bank
2+00	6.7												Ground Shot
2+12	0.5												Edge of Water
2+67	-7.8												River Bottom
2+87	-20.7												River Bottom
3+09	-21.3												River Bottom
3+30	-20.0												River Bottom
3+55	-19.4												River Bottom
3+76	-19.0												River Bottom
4+00	-17.8												River Bottom
4+21	-18.0												River Bottom
4+45	-18.7												River Bottom
4+70	-19.0												River Bottom
4+94	-18.4												River Bottom
5+21	-17.3												River Bottom
5+45	-16.1												River Bottom
5+69	-14.6												River Bottom
5+96	-13.5												River Bottom
6+20	-13.7												River Bottom
6+47	-12.5												River Bottom
6+71	-12.1												River Bottom
6+99	-11.9												River Bottom
7+23	-12.4												River Bottom
7+48	-12.2												River Bottom
7+70	-12.9												River Bottom
7+94	-11.2												River Bottom
8+15	-6.8												River Bottom
8+74	0.4												Edge of Water
9+00	1.6												Sand Bar
10+00	3.6												Sand Bar
11+00	5.4												Edge of Vegetation
12+00	5.1												Ground Shot
13+00	4.8												Ground Shot
14+00	4.6												Ground Shot
14+84	3.7												Toe of Bank
14+96	7.7												Top of Bank
15+00	7.8												Ground Shot

Calc'd By: CZ
Date: 10/03/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
15+38	8.6													Ground Shot
15+53	9.1													Grade Break
15+71	7.2													Grade Break
16+00	6.7													Ground Shot
16+88	7.2													Ground Shot




STA	2013	Future	Description										
0+00	10.9												Ground Shot
1+00	10.4												Ground Shot
1+50	8.7												Ground Shot
1+79	8.6												Top of Bank
1+89	0.6												Edge of Water
2+01	-10.6												River Bottom
2+16	-19.0												River Bottom
2+36	-30.7												River Bottom
2+59	-33.6												River Bottom
2+82	-35.3												River Bottom
3+08	-32.7												River Bottom
3+28	-31.4												River Bottom
3+54	-30.9												River Bottom
3+77	-30.0												River Bottom
4+00	-30.0												River Bottom
4+23	-27.8												River Bottom
4+48	-25.6												River Bottom
4+68	-22.7												River Bottom
4+94	-20.1												River Bottom
5+16	-17.5												River Bottom
5+40	-14.9												River Bottom
5+62	-13.5												River Bottom
5+82	-10.5												River Bottom
6+02	-6.1												River Bottom
6+50	0.2												Edge of Water
7+00	2.9												Sand Bar
7+90	4.9												Edge of Vegetation
8+00	4.9												Ground Shot
9+00	5.5												Ground Shot
10+00	5.1												Ground Shot
11+00	5.6												Ground Shot
12+00	5.8												Ground Shot
13+00	5.5												Ground Shot
14+00	6.2												Ground Shot
15+00	6.1												Ground Shot
16+00	6.3												Edge of Vegetation
16+52	6.7												Grade Break
16+62	8.0												Grade Break
16+89	9.1												Ground Shot

Calc'd By: CZ
Date: 10/03/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
17+00	8.9													Ground Shot
18+00	9.0													Ground Shot
18+39	10.2													Ground Shot




STA	2013	Future	Description										
0+00	11.0												Ground Shot
1+00	11.3												Ground Shot
2+00	9.9												Ground Shot
2+08	10.0												Top of Bank
2+22	4.9												Toe of Bank
3+00	2.2												Sand Bar
4+00	1.5												Sand Bar
5+00	1.8												Sand Bar
5+56	0.4												Edge of Water
5+79	-4.7												River Bottom
5+85	-5.1												River Bottom
6+10	-9.0												River Bottom
6+36	-17.5												River Bottom
6+54	-24.6												River Bottom
6+85	-28.6												River Bottom
7+08	-32.0												River Bottom
7+31	-33.5												River Bottom
7+57	-33.9												River Bottom
7+83	-33.0												River Bottom
8+06	-32.1												River Bottom
8+29	-31.0												River Bottom
8+56	-31.1												River Bottom
8+79	-31.3												River Bottom
9+02	-30.7												River Bottom
9+28	-29.9												River Bottom
9+51	-27.1												River Bottom
9+72	-23.2												River Bottom
10+00	-20.1												River Bottom
10+23	-3.0												River Bottom
10+43	-3.2												River Bottom
10+94	0.6												Edge of Water
11+05	9.5												Top of Bank
12+00	9.4												Ground Shot
13+00	7.9												Edge of Vegetation
14+01	6.9												Ground Shot
15+01	7.2												Ground Shot
16+00	7.8												Ground Shot
17+01	8.3												Ground Shot
18+00	7.0												Ground Shot
19+00	6.3												Ground Shot

Calc'd By: CZ
Date: 10/03/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description										
20+00	6.7												Ground Shot
21+00	6.7												Ground Shot
21+85	7.0												Toe of Bank
22+00	8.2												Top of Bank
22+16	8.8												Ground Shot
23+00	9.7												Ground Shot
23+67	10.2												Ground Shot



STA	2013	Future	Description										
0+00	7.5												Ground Shot
1+00	8.5												Ground Shot
1+50	8.9												Ground Shot
2+00	9.0												Ground Shot
2+34	8.0												Edge of Vegetation
3+00	7.2												Ground Shot
4+00	7.2												Ground Shot
4+36	7.7												Edge of Vegetation
5+00	8.6												Ground Shot
6+00	10.1												Ground Shot
7+00	10.9												Ground Shot
7+11	11.7												Grade Break
7+95	20.5												Grade Break
8+00	19.6												Ground Shot
9+00	19.3												Top of Bank
9+67	8.1												Toe of Bank
10+00	6.5												Sand Bar
11+00	4.2												Sand Bar
12+00	5.2												Sand Bar
13+00	1.8												Sand Bar
14+00	3.8												Sand Bar
15+00	2.6												Sand Bar
16+00	1.8												Sand Bar
17+00	1.3												Sand Bar
18+01	1.0												Sand Bar
19+00	0.0												Sand Bar
20+00	-0.6												Sand Bar
21+00	-0.8												Sand Bar
22+00	-1.0												Sand Bar
23+00	-0.7												Sand Bar
24+00	-1.3												Sand Bar
25+00	-1.1												Sand Bar
26+00	-0.9												Sand Bar
27+00	-0.2												Sand Bar
28+00	0.6												Sand Bar
29+00	0.5												Sand Bar
30+00	0.0												Sand Bar
31+00	0.3												Sand Bar
32+00	-0.3												Sand Bar
33+00	-1.0												Sand Bar


STA	2013	Future	Description										
34+00	-1.6												Sand Bar
35+00	-1.9												Sand Bar
35+11	-2.7												Edge of Water
36+19	-3.2												River Bottom
36+39	-5.3												River Bottom
36+59	-7.8												River Bottom
36+79	-10.9												River Bottom
37+07	-13.3												River Bottom
37+30	-16.2												River Bottom
37+59	-18.8												River Bottom
37+84	-20.2												River Bottom
38+16	-20.8												River Bottom
38+38	-21.1												River Bottom
38+70	-22.1												River Bottom
38+92	-24.2												River Bottom
39+21	-22.6												River Bottom
39+38	-3.7												River Bottom
39+77	-3.0												Edge of Water
39+89	5.6												Top of Bank
40+00	5.6												Ground Shot
41+00	5.0												Ground Shot
42+00	4.9												Ground Shot
43+00	4.9												Ground Shot
43+53	3.5												Edge of Vegetation
44+00	2.1												Top of Bank
45+00	-2.5												Sand Bar
45+15	-2.9												Edge of Water
45+19	0.4												River Bottom
45+64	-1.5												River Bottom
46+13	-6.5												River Bottom
46+62	-10.0												River Bottom
47+14	-10.3												River Bottom
47+65	-7.8												River Bottom
48+13	-5.2												River Bottom
48+65	-1.5												River Bottom
49+17	-3.3												Edge of Water
49+22	3.6												Top of Bank
49+53	4.5												Grade Break
50+00	5.2												Ground Shot
50+14	8.57												Ground Shot

Calc'd By: CZ
Date: 10/03/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
50+28	8.09													Grade Break
50+33	5.84													Grade Break
50+36	7.50													Grade Break
51+00	7.55													Ground Shot
51+30	7.35													Grade Break
51+34	6.05													Grade Break
51+44	7.01													Ground Shot

Transect 13


STA	2013	Future	Description										
0+00	10.1												Ground Shot
1+00	10.4												Ground Shot
1+65	12.6												Ground Shot
2+00	13.6												Ground Shot
3+00	15.6												Ground Shot
3+67	16.9												Ground Shot
4+00	16.1												Ground Shot
4+76	16.1												Top of Bank
5+19	9.1												Toe of Bank
6+00	6.5												Edge of Vegetation
7+00	3.0												Edge of Vegetation
8+00	0.1												Sand Bar
9+00	-0.3												Sand Bar
10+00	-1.5												Sand Bar
11+00	-2.6												Sand Bar
11+24	-3.3												Edge of Water
13+87	-2.6												River Bottom
14+03	-2.7												River Bottom
14+20	-3.2												River Bottom
14+36	-2.4												River Bottom
14+52	-3.0												River Bottom
14+68	-3.0												River Bottom
14+88	-2.4												River Bottom
15+04	-3.1												River Bottom
15+24	-2.9												River Bottom
15+36	-2.9												River Bottom
15+53	-2.3												River Bottom
15+66	-2.4												River Bottom
15+76	-2.7												River Bottom
15+89	-3.4												River Bottom
16+05	-3.5												River Bottom
16+18	-3.8												River Bottom
16+38	-3.9												River Bottom
16+54	-3.4												River Bottom
16+92	-3.5												Edge of Water
17+31	-1.1												Sand Bar
18+00	-0.7												Sand Bar
19+00	-0.9												Sand Bar
20+00	-0.9												Sand Bar
21+01	-1.0												Sand Bar

Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description										
22+00	-1.1												Sand Bar
23+00	-2.4												Sand Bar
24+00	-2.9												Sand Bar
24+35	-4.4												Edge of Water
24+48	-2.7												River Bottom
24+64	-5.5												River Bottom
24+87	-9.0												River Bottom
25+10	-9.6												River Bottom
25+33	-9.9												River Bottom
25+56	-9.9												River Bottom
25+82	-10.2												River Bottom
26+01	-10.4												River Bottom
26+24	-10.0												River Bottom
26+50	-10.0												River Bottom
26+70	-10.6												River Bottom
26+89	-11.6												River Bottom
27+15	-11.1												River Bottom
27+35	-10.8												River Bottom
27+76	-2.8												Edge of Water
27+87	5.9												Top of Bank
28+00	6.7												Ground Shot
28+44	6.9												Ground Shot
29+00	6.5												Ground Shot
29+94	6.6												Ground Shot




STA	2013	Future	Description										
0+00	13.8												Ground Shot
1+00	12.3												Ground Shot
1+00	15.3												Ground Shot
1+50	16.7												Ground Shot
1+95	15.1												Top of Bank
2+11	3.3												Toe of Bank
2+21	0.9												Edge of Water
2+88	-2.9												River Bottom
3+09	-3.3												River Bottom
3+30	-3.8												River Bottom
3+50	-4.0												River Bottom
3+71	-4.1												River Bottom
3+91	-4.4												River Bottom
4+12	-4.4												River Bottom
4+36	-4.2												River Bottom
4+57	-4.7												River Bottom
4+81	-3.9												River Bottom
5+01	-3.2												River Bottom
11+47	-2.4												River Bottom
11+64	-2.4												River Bottom
11+81	-2.5												River Bottom
11+98	-3.3												River Bottom
12+16	-3.6												River Bottom
12+36	-4.0												River Bottom
12+57	-4.6												River Bottom
12+77	-4.7												River Bottom
13+01	-4.9												River Bottom
13+29	-5.6												River Bottom
13+56	-5.8												River Bottom
13+80	-6.4												River Bottom
14+08	-6.5												River Bottom
14+35	-6.8												River Bottom
14+59	-6.5												River Bottom
14+87	-6.2												River Bottom
15+14	-5.2												River Bottom
15+42	-5.4												River Bottom
15+66	-5.1												River Bottom
15+93	-6.1												River Bottom
16+24	-8.3												River Bottom
16+52	-8.3												River Bottom

Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1


CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1


STA	2013	Future	Description											
16+79	-5.1													River Bottom
17+03	-2.8													River Bottom
17+55	0.8													Edge of Water
17+79	1.9													Sand Bar
17+97	4.4													Sand Bar
18+19	5.6													Toe of Bank
18+35	11.9													Top of Bank
18+91	12.6													Ground Shot
19+41	12.5													Ground Shot



STA	2013	Future	Description										
0+00	10.0												Ground Shot
0+50	9.4												Ground Shot
1+00	8.4												Top of Bank
1+12	0.8												Edge of Water
1+28	-3.1												River Bottom
1+37	-4.2												River Bottom
1+46	-7.0												River Bottom
1+58	-6.5												River Bottom
1+70	-7.5												River Bottom
1+81	-10.7												River Bottom
1+91	-12.3												River Bottom
2+06	-8.3												River Bottom
2+17	-6.6												River Bottom
2+27	-5.0												River Bottom
2+37	-2.1												River Bottom
2+47	0.8												Edge of Water
2+68	3.4												Sand Bar
3+10	4.7												Edge of Vegetation
3+59	6.7												Edge of Vegetation
4+00	7.9												Ground Shot
4+18	8.9												Ground Shot
4+68	9.2												Ground Shot



STA	2013	Future	Description										
0+00	8.6												Ground Shot
0+50	8.5												Ground Shot
1+16	8.0												Top of Bank
1+47	3.7												Edge of Vegetation
1+66	0.9												Edge of Water
1+93	-2.1												River Bottom
2+08	-2.2												River Bottom
2+19	-2.6												River Bottom
2+29	-2.9												River Bottom
2+39	-3.1												River Bottom
2+49	-3.2												River Bottom
2+66	-3.5												River Bottom
2+83	-3.5												River Bottom
2+91	-3.3												River Bottom
3+08	-3.1												River Bottom
3+27	-2.4												River Bottom
3+68	0.7												Edge of Water
3+82	6.3												Top of Bank
4+29	8.6												Ground Shot
4+79	8.5												Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1


CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0+00	8.6													Ground Shot
0+50	8.6													Ground Shot
1+00	7.9													Ground Shot
1+58	7.1													Top of Bank
1+76	6.3													Edge of Vegetation
2+14	3.7													Edge of Vegetation
2+50	1.0													Edge of Water
3+17	-2.6													River Bottom
3+26	-2.8													River Bottom
3+38	-3.2													River Bottom
3+52	-2.1													River Bottom
3+68	-3.6													River Bottom
3+80	-4.0													River Bottom
3+93	-3.9													River Bottom
4+01	-3.5													River Bottom
4+14	-3.0													River Bottom
4+22	-3.0													River Bottom
4+57	0.9													Edge of Water
4+76	7.1													Top of Bank
5+33	7.8													Ground Shot
5+83	8.0													Ground Shot



STA	2013	Future	Description										
0+00	8.6												Ground Shot
0+50	8.5												Ground Shot
0+95	7.9												Top of Bank
1+15	3.3												Edge of Vegetation
1+49	0.7												Edge of Water
1+88	-1.9												River Bottom
1+99	-2.2												Edge of Water
2+19	-2.3												River Bottom
2+29	-2.5												Edge of Water
2+40	-2.5												River Bottom
2+61	-2.4												Edge of Water
2+75	-4.5												River Bottom
2+88	-4.1												Edge of Water
2+96	-2.7												River Bottom
3+50	0.7												Edge of Water
3+69	7.0												Top of Bank
4+20	8.5												Ground Shot
4+70	8.1												Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0+00	13.8													Ground Shot
0+15	16.8													Ground Shot
0+50	15.5													Ground Shot
1+13	11.4													Top of Bank
1+36	0.5													Edge of Water
1+63	-0.7													River Bottom
1+99	-0.6													River Bottom
2+30	-0.8													River Bottom
2+50	-0.9													River Bottom
2+99	-1.3													River Bottom
3+30	-1.3													River Bottom
3+56	0.6													Edge of Water
3+93	6.6													Top of Bank
4+53	7.4													Ground Shot
5+03	7.5													Ground Shot



STA	2013	Future	Description											
0+00	24.6													Ground Shot
0+50	20.8													Ground Shot
1+02	9.5													Ground Shot
1+24	7.2													Top of Bank
1+37	0.5													Edge of Water
1+46	-1.0													River Bottom
1+58	-2.1													River Bottom
1+75	-2.1													River Bottom
2+00	-1.8													River Bottom
2+24	-1.6													River Bottom
2+50	-1.1													River Bottom
3+22	0.5													Edge of Water
3+41	3.3													Grade Break
3+64	4.2													Toe of Bank
3+79	8.6													Top of Bank
4+04	9.7													Grade Break
4+58	9.1													Ground Shot
5+08	8.7													Ground Shot


Calc'd By: CZ

Date: 10/04/13

RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
Doc: LCMF-156 REV1



Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0.00	26.017													Ground Shot
6.85	23.035													Ground Shot
59.76	24.037													Ground Shot
109.87	23.087													Top of Bank
135.55	2.572													Toe of Bank
147.55	0.599													Edge of Water
166.87	-1.109													River Bottom
200.00	-1.103													River Bottom
224.35	-1.593													River Bottom
249.69	-1.621													River Bottom
274.94	-1.382													River Bottom
300.64	-0.692													River Bottom
337.89	0.551													Edge of Water
361.08	4.418													Toe of Bank
368.27	8.600													Top of Bank
387.66	10.466													Ground Shot
427.42	9.059													Ground Shot
477.44	8.593													Ground Shot


Calc'd By: CZ

Date: 10/04/13

RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
Doc: LCMF-156 REV1




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0+00	25.2													Ground Shot
0+50	25.1													Ground Shot
1+06	23.2													Top of Bank
1+34	3.2													Toe of Bank
1+53	0.5													Edge of Water
2+25	-1.1													River Bottom
2+51	-1.7													River Bottom
2+75	-1.7													River Bottom
3+00	-1.5													River Bottom
3+27	-1.2													River Bottom
3+40	0.7													Edge of Water
3+44	2.2													Grade Break
3+84	6.1													Edge of Vegetation
3+95	7.7													Top of Bank
4+50	7.9													Ground Shot
5+00	10.0													Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1


CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description										
0+00	26.5												Ground Shot
0+50	27.0												Ground Shot
0+94	27.9												Ground Shot
1+13	25.3												Top of Bank
1+45	2.6												Toe of Bank
1+56	0.2												Edge of Water
2+26	-1.7												River Bottom
2+39	-2.4												River Bottom
2+48	-2.0												River Bottom
2+61	-2.1												River Bottom
2+74	-2.2												River Bottom
2+90	-3.0												River Bottom
3+00	-3.0												River Bottom
3+17	-2.6												River Bottom
3+44	0.3												Edge of Water
3+86	5.9												Edge of Vegetation
3+96	7.1												Top of Bank
4+65	8.7												Ground Shot
5+15	9.4												Ground Shot



STA	2013	Future	Description										
0+00	27.5												Ground Shot
0+50	26.4												Ground Shot
0+70	26.8												Ground Shot
0+89	21.8												Grade Break
1+00	25.7												Top of Bank
1+31	2.8												Toe of Bank
1+47	0.6												Edge of Water
2+19	-2.6												River Bottom
2+38	-2.2												River Bottom
2+48	-2.2												River Bottom
2+61	-2.4												River Bottom
2+72	-2.8												River Bottom
2+89	-2.7												River Bottom
2+97	-2.6												River Bottom
3+07	-2.7												River Bottom
3+35	0.1												Edge of Water
3+51	2.5												Ground Shot
3+81	6.1												Edge of Vegetation
3+91	7.8												Top of Bank
4+53	8.5												Ground Shot
5+03	8.4												Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0+00	24.0													Ground Shot
0+60	24.1													Ground Shot
0+85	24.0													Ground Shot
1+03	21.5													Grade Break
1+36	2.7													Top of Bank
1+58	0.4													Toe of Bank
2+19	-2.5													Edge of Water
2+32	-2.6													River Bottom
2+43	-2.5													River Bottom
2+53	-2.4													River Bottom
2+63	-2.4													River Bottom
2+80	-2.3													River Bottom
2+91	-2.0													River Bottom
3+08	-2.2													River Bottom
3+36	0.2													River Bottom
3+57	3.2													Edge of Water
3+89	6.1													Ground Shot
3+97	7.1													Edge of Vegetation
4+79	8.3													Top of Bank
5+29	9.8													Ground Shot
														Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1


CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0+00	27.0													Ground Shot
0+50	27.1													Ground Shot
0+74	24.3													Grade Break
0+82	26.6													Grade Break
0+98	26.0													Top of Bank
1+30	2.5													Toe of Bank
1+46	0.1													Edge of Water
2+20	-2.4													River Bottom
2+31	-2.3													River Bottom
2+41	-3.3													River Bottom
2+48	-2.0													River Bottom
2+58	-2.7													River Bottom
2+65	-2.9													River Bottom
2+72	-3.1													River Bottom
2+78	-2.9													River Bottom
2+85	-2.5													River Bottom
2+92	-2.1													River Bottom
3+17	-0.1													Edge of Water
3+39	1.9													Ground Shot
3+52	4.7													Ground Shot
3+76	5.9													Edge of Vegetation
3+89	7.0													Top of Bank
4+10	8.0													Ground Shot
4+71	8.0													Ground Shot
5+21	9.7													Ground Shot



STA	2013	Future	Description										
0+00	21.0												Ground Shot
0+50	21.3												Ground Shot
0+83	21.5												Ground Shot
1+06	20.7												Top of Bank
1+31	1.0												Toe of Bank
1+34	0.0												Edge of Water
1+37	-3.0												River Bottom
1+44	-4.2												River Bottom
1+51	-4.4												River Bottom
1+61	-4.0												River Bottom
1+75	-3.6												River Bottom
1+89	-3.4												River Bottom
1+99	-3.0												River Bottom
2+16	-3.2												River Bottom
2+33	-3.2												River Bottom
2+44	-2.6												River Bottom
2+64	0.1												Edge of Water
3+40	2.5												Ground Shot
3+65	5.7												Edge of Vegetation
3+81	7.6												Top of Bank
4+26	8.2												Ground Shot
4+81	8.4												Ground Shot
5+31	9.2												Ground Shot



Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0.12	24.314													Ground Shot
50.01	23.604													Ground Shot
100.96	22.981													Top of Bank
130.14	0.233													Edge of Water
142.85	-8.100													River Bottom
188.57	-7.900													River Bottom
208.61	-5.200													River Bottom
224.28	-2.500													River Bottom
244.77	0.090													Edge of Water
282.47	2.575													Ground Shot
329.56	2.945													Ground Shot
388.29	5.835													Edge of Vegetation
401.34	8.033													Top of Bank
447.08	7.653													Ground Shot
485.46	8.397													Ground Shot
535.60	9.537													Ground Shot


Calc'd By: CZ

Date: 10/04/13


RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects


Kuukpik/LCMF
Alpine Survey Office
Doc: LCMF-156 REV1




STA	2013	Future	Description										
0+00	23.7												Ground Shot
0+69	21.7												Top of Bank
0+79	19.3												Grade Break
1+00	6.0												Toe of Bank
1+16	4.4												Top of Bank
1+17	3.3												Toe of Bank
1+52	0.2												Edge of Water
1+63	-2.9												River Bottom
1+75	-4.0												River Bottom
1+87	-5.9												River Bottom
1+99	-5.8												River Bottom
2+12	-6.4												River Bottom
2+26	-5.7												River Bottom
2+36	-5.3												River Bottom
2+48	-3.4												River Bottom
2+61	-2.7												River Bottom
2+73	-2.1												River Bottom
2+81	-2.8												River Bottom
3+06	-0.5												Edge of Water
3+84	4.3												Sand Bar
3+94	5.9												Grade Break
4+30	6.1												Edge of Vegetation
4+67	8.8												Grade Break
5+22	8.1												Grade Break
5+58	9.4												Grade Break/Edge of Veg
5+77	9.6												Ground Shot
6+27	10.1												Ground Shot



STA	2013	Future	Description										
0+00	8.6												Ground Shot
0+50	9.6												Ground Shot
1+06	8.1												Edge of Vegetation
1+29	8.4												Top of Bank
1+40	5.7												Toe of Bank
1+85	5.7												Ground Shot
2+37	6.0												Ground Shot
2+89	6.9												Ground Shot
3+16	7.7												Ground Shot
3+70	8.0												Top of Bank
3+80	6.7												Grade Break/Edge of Veg
4+06	3.8												Sand Bar
4+43	1.4												Grade Break
4+62	-0.2												Edge of Water
4+71	-2.6												River Bottom
4+81	-2.8												River Bottom
4+92	-2.1												River Bottom
5+02	-2.1												River Bottom
5+10	-2.6												River Bottom
5+20	-2.3												River Bottom
5+29	-2.2												River Bottom
5+39	-2.1												River Bottom
5+50	-2.2												River Bottom
5+60	-2.1												River Bottom
5+70	-2.5												River Bottom
5+79	-2.2												River Bottom
6+03	0.0												Edge of Water
6+20	2.6												Toe of Bank
6+32	8.4												Top of Bank
6+83	9.2												Grade Break
7+31	10.9												Edge of Vegetation
7+54	11.2												Ground Shot
8+04	10.7												Ground Shot



STA	2013	Future	Description										
0+00	8.4												Ground Shot
0+50	7.8												Ground Shot
0+96	7.0												Ground Shot
1+50	7.2												Ground Shot
2+00	7.4												Ground Shot
2+50	8.0												Ground Shot
3+12	6.8												Edge of Vegetation
3+32	6.4												Top of Bank
4+03	0.1												Edge of Water
4+07	-0.8												River Bottom
4+16	-2.7												River Bottom
4+26	-2.5												River Bottom
4+36	-3.9												River Bottom
4+47	-5.4												River Bottom
4+57	-6.6												River Bottom
4+68	-7.0												River Bottom
4+79	-6.1												River Bottom
4+98	-0.4												Edge of Water
5+10	8.5												Top of Bank
5+40	10.4												Ground Shot
5+79	10.2												Ground Shot
6+21	11.5												Ground Shot
6+71	10.8												Ground Shot


Transect 32

Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1


CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1


STA	2013	Future	Description											
0+00	9.9													Ground Shot
0+50	8.6													Ground Shot
1+03	8.5													Edge of Vegetation
1+52	10.6													Grade Break
2+00	9.9													Ground Shot
2+57	7.9													Top of Bank
2+67	6.9													Edge of Vegetation
2+78	5.4													Sand Bar
2+87	3.5													Grade Break
3+57	0.0													Edge of Water
3+81	-3.2													River Bottom
4+04	-2.2													River Bottom
4+18	-3.5													River Bottom
4+38	-4.4													River Bottom
4+59	-3.1													River Bottom
4+78	-0.1													Edge of Water
4+99	9.1													Top of Bank
5+53	9.7													Edge of Vegetation
6+02	10.1													Ground Shot
6+41	10.5													Ground Shot
7+11	10.7													Ground Shot

Transect 33


STA	2013	Future	Description										
0+00	12.6												Ground Shot
0+50	12.6												Ground Shot
1+00	10.3												Ground Shot
1+50	9.2												Ground Shot
2+12	8.1												Top of Bank
2+15	3.5												Toe of Bank
2+23	-0.3												Edge of Water
2+30	-4.6												River Bottom
2+37	-7.2												River Bottom
2+48	-7.3												River Bottom
2+58	-6.9												River Bottom
2+72	-6.7												River Bottom
2+82	-3.2												River Bottom
2+96	-2.2												River Bottom
3+06	-1.9												River Bottom
3+27	0.1												Edge of Water
3+66	4.5												Grade Break
3+94	5.6												Sand Bar
4+29	7.1												Edge of Vegetation
4+39	8.4												Top of Bank
4+50	8.6												Ground Shot
5+00	9.0												Ground Shot
5+50	7.4												Ground Shot
6+00	9.7												Ground Shot
6+30	10.1												Edge of Vegetation
6+64	9.9												Ground Shot
7+00	10.6												Ground Shot
7+50	10.1												Ground Shot

Transect 34

STA	2013	Future	Description										
0.00	12.558												Ground Shot
50.08	12.952												Ground Shot
99.75	11.233												Ground Shot
110.73	11.411												Grade Break
124.77	9.384												Grade Break
164.52	10.284												Grade Break
180.68	8.140												Grade Break
226.50	9.279												Grade Break
250.65	10.434												Grade Break
272.34	8.248												Grade Break
314.93	8.003												Grade Break
358.54	6.895												Edge of Vegetation
379.06	6.609												Top of Bank
391.71	3.505												Sand Bar
429.30	-0.066												Edge of Water
459.71	-2.300												River Bottom
485.77	-4.600												River Bottom
508.74	-5.100												River Bottom
525.50	-2.000												River Bottom
543.55	-0.188												Edge of Water
547.01	0.152												Toe of Bank
558.45	7.551												Top of Bank
572.28	9.715												Grade Break
586.45	9.239												Edge of Vegetation
628.41	9.358												Ground Shot
669.12	9.455												Ground Shot
719.01	10.276												Ground Shot



STA	2013	Future	Description										
0+00	8.3												Ground Shot
0+50	8.0												Ground Shot
0+81	7.2												Ground Shot
1+17	7.2												Top of Bank
1+23	6.3												Edge of Vegetation
1+48	4.6												Edge of Water
1+52	4.0												River Bottom
1+89	0.8												River Bottom
2+20	-0.9												River Bottom
2+48	-1.7												River Bottom
2+95	-3.0												River Bottom
3+49	-2.1												River Bottom
3+78	1.7												River Bottom
3+90	2.5												River Bottom
3+96	4.8												Edge of Water
4+06	8.6												Top of Bank
5+03	9.5												Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0+00	8.0													Ground Shot
0+50	8.3													Ground Shot
0+92	7.0													Top of Bank
1+03	6.5													Edge of Vegetation
1+40	4.6													Edge of Water
1+59	2.2													River Bottom
2+01	0.5													River Bottom
2+48	-2.4													River Bottom
2+99	-2.9													River Bottom
3+45	-1.6													River Bottom
3+84	2.1													River Bottom
3+95	4.6													Edge of Water
4+04	9.1													Top of Bank
4+49	8.8													Ground Shot
4+99	9.5													Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description											
0+00	8.1													Ground Shot
0+50	7.9													Ground Shot
0+81	7.3													Top of Bank
1+22	6.1													Edge of Vegetation
1+48	4.6													Edge of Water
1+94	1.4													River Bottom
2+46	0.4													River Bottom
2+96	-2.6													River Bottom
3+47	-2.8													River Bottom
3+95	0.8													River Bottom
4+22	4.7													Edge of Water
4+31	9.3													Top of Bank
4+79	9.0													Ground Shot
5+29	9.2													Ground Shot




Calc'd By: CZ
Date: 10/04/2013
RPT-CE-CD-113 REV1

CD-5 Michael Baker
Bridge Transects

Kuukpik/LCMF
Alpine Survey Office
DOC LCMF-156 REV1

STA	2013	Future	Description										
0+00	8.5												Ground Shot
0+50	7.6												Ground Shot
0+79	6.7												Top of Bank
0+89	5.8												Edge of Vegetation
1+06	4.4												Edge of Water
1+27	1.3												River Bottom
1+54	0.1												River Bottom
2+01	-1.2												River Bottom
2+47	-1.7												River Bottom
3+01	-3.0												River Bottom
3+55	-0.3												River Bottom
3+71	1.8												River Bottom
3+91	4.6												Edge of Water
4+03	9.3												Top of Bank
4+43	9.4												Ground Shot
4+93	9.6												Ground Shot



Project Note

Baker

Page | B.1

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

Attachment B

Daily Field Reports

Project Note

Baker

Page | B.2

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

This page intentionally blank

08-21-2013 Daily Field Summary

Project Name(s)	2013 ASDP Water Quality Monitoring/CD5 Bank Erosion Survey		Date	2013-08-21		
Project Number(s)	136068/135141	Document No.				
Submitted by	Garrett Yager					
Field Personnel	Garrett Yager, Sarah Case					
Subcontractor	Bristow, LCMF					
Afternoon Check-In	1400	Contact Person	Helicopter Coordinator			
Evening Check-In	1930	Contact Person	Karen Brown			
Wind		Temperature		Sky		
Calm		40°F		Partly Cloudy		
Health & Safety						
A Baker Tailgate and Task Hazard Assessment meeting was conducted at 0700 hours. A Helicopter Toolbox meeting was conducted at 1300 hours.						
Summary of Events						
Garrett Yager and Sarah Case demobilized the ASDP Water Quality Monitoring project. Ms. Case departed Alpine for Anchorage at 1600 hours. Mr. Yager departed CD2 via helicopter at 1400 hours for a rendezvous with LCMF at the Nigliagvik CD5 crossing. A detailed bank delineation survey of the CD5 crossing was completed at the upstream, downstream, east bank, and west bank locations. Mr. Yager traveled back by boat to CD4 with LCMF.						
Challenges						
None						
Comments						
Water samples are being stored in the refrigerator space at the waste water treatment plant.						
Planned for Next Field Day						
Mr. Yager will remain at Alpine to work on CD5 erosion monitoring tasks on the Nigliq Channel before departing for Anchorage.						

Daily Photo (s)



Photo 1: Whisker placed at the edge of the west bank on the Nigliagvik; August 21, 2013



Photo 2: Surveying the edge of the west bank of the Nigliagvik with Real Time Kinematic GPS; August 21, 2013

08-22-2013 Daily Field Summary

Project Name(s)	2013 ASDP Water Quality Monitoring/CD5 Bank Erosion Survey		Date	2013-08-22
Project Number(s)	136068/135141	Document No.		
Submitted by	Garrett Yager			
Field Personnel	Garrett Yager			
Subcontractor	LCMF			
Afternoon Check-In	1100	Contact Person	Alpine Security	
Evening Check-In	1600	Contact Person	Alpine Security	
Wind	Temperature		Sky	
7 mph, WNW	35°F		Overcast	
Health & Safety				
Safety meeting 0600 hours: LCMF Safety Meeting and Float Plan.				
Summary of Events				
ASDP water samples were packaged and checked-in as baggage for Mr. Yager's return flight to Anchorage. At 1100 hours, Mr. Yager accompanied LCMF to the Nigliq Channel CD5 crossing via boat. The detailed bank delineation survey was completed at the Nigliq Channel crossing. The west bank of the Nigliq Channel upstream and downstream of the proposed CD5 crossing was surveyed. The east bank of the Nigliq Channel downstream of the proposed CD5 crossing was surveyed. The east bank survey was limited to the downstream section because of restricted access upstream of the proposed CD5 crossing.				
Challenges				
Water samples were scrutinized by the Transportation Security Administration and Shared Services because of unknown quantities of the acid preservative in the sample bottles. The samples were eventually cleared for the flight back to Anchorage.				
Comments				
None				
Planned for Next Field Day				
Drop ASDP water samples off at SGS laboratory.				

Daily Photo (s)



**Photo 1: Surveying the edge of the west bank of the Nigliq Channel with
Real Time Kinematic GPS; August 22, 2013**



**Photo 2: The east bank of the Nigliq Channel downstream of the
proposed CD5 crossing; August 22, 2013**

Project Note

Baker

Page | C.1

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

Attachment C

Nigliq Channel Bank Surveys


Project Note

Baker

Page | C.2

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

This page intentionally blank



Alpine AP00
East Bank Nigliq
 Streambank Monitor

Baseline	East Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/22/2013	Future	Date								
0+00	169.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
1+00	174.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
2+00	178.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
3+00	191.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
4+00	188.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
5+00	196.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
6+00	201.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

Alpine AP00
East Bank Nigliq
 Streambank Monitor

Baseline	East Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/22/2013	Future	Date								
7+00	208.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
8+00	199.8										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
9+00	406.2										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
10+00	280.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
11+00	192.2										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
12+00	100.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
13+00	192.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

Alpine AP00
East Bank Nigliq
Streambank Monitor

Baseline	East Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/22/2013	Future	Date								
14+00	210.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
15+00	192.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
15+56	195.4										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

***Note: Survey completed on 8/22/13 was used for baseline data to compute Incremental/Cumulative Change. Negative numbers indicate erosion.

Alpine AP00
West Bank Nigliq
 Streambank Monitor

Baseline	West Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
0+00	180.2										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
1+00	191.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
2+00	193.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
3+00	189.2										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
4+00	192.2										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
5+00	202.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
6+00	224.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

Alpine AP00
West Bank Nigliq
 Streambank Monitor

Baseline	West Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
7+00	228.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
8+00	232.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
9+00	220.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
10+00	216.8										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
11+00	209.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
12+00	199.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
13+00	192.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

Alpine AP00
West Bank Nigliq
 Streambank Monitor

Baseline	West Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
14+00	200.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
15+00	190.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
16+00	211.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
17+00	204.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
18+00	212.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
19+00	221.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
20+00	232.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

Alpine AP00
West Bank Nigliq
Streambank Monitor

Baseline	West Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
21+00	233.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
22+00	237.8										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
23+00	237.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
24+00	229.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
25+00	214.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
25+11	213.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

*****Note:** Survey completed on 8/22/13 was used for baseline data to compute Incremental/Cumulative Change. Negative numbers indicate erosion.

Project Note

Baker

Page | D.1

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

Attachment D

Nigliagvik Bank Surveys


Project Note

Baker

Page | D.2

CD5 Bank Erosion, Channel Bathymetry, and Bridge Bathymetry Monitoring

This page intentionally blank



Alpine AP00
East Bank Nigliagvik
 Streambank Monitor

Baseline	East Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
0+00	165.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
1+00	185.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
2+00	165.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
3+00	188.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
4+00	154.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
5+00	141.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
6+00	120.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

Alpine AP00
East Bank Nigliagvik
Streambank Monitor

Baseline	East Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
7+00	119.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
8+00	120.9										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
8+91	115.7										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

***Note: Survey completed on 8/21/13 was used for baseline data to compute Incremental/Cumulative Change. Negative numbers indicate erosion.

Alpine AP00
West Bank Nigliagvik
 Streambank Monitor

Baseline	West Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
0+00	110.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
1+00	103.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
2+00	99.6										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
3+00	98.8										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
4+00	106.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
5+00	102.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
6+00	92.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

Alpine AP00
West Bank Nigliagvik
 Streambank Monitor

Baseline	West Bank Monitor - Top of Bank Locations										Description
Station	See Drawing CE-AP00-1126 Rev 1 for Survey Baseline Location										
	8/21/2013	Future	Date								
7+00	107.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
8+00	115.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
9+00	96.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
10+00	106.1										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change
10+28	112.0										Baseline Offset (In Feet)
											Incremental Change
											Cumulative Change

*****Note:** Survey completed on 8/21/13 was used for baseline data to compute Incremental/Cumulative Change. Negative numbers indicate erosion.